

DRAFT

LEGEND

- Proposed Path /Road
- Proposed Garden Bed
- Proposed Crypts
- New grave
- Proposed Building
- Lawn/Reinforced lawn
- Proposed Trees
- Refer Enlargements

0 25 50m

AREA (1) : WEST END

- CARRY OUT A DETAILED GEOTECHNICAL TEST OVER THE ENTIRE AREA TO MAP OUT VARIATIONS IN DEPTH AND ASCERTAIN SOIL CONSTRAINTS.
- THE AREA WILL ONLY BE USED FOR BURIAL IF GEOTECHNICAL CONDITIONS ALLOW.
- EXTEND VEHICULAR ROAD FOR MAINTENANCE AND DISABLED ACCESS (3M WIDE). PROVIDE TWO DEDICATED DISABLED CARPARKING BAYS FOR PEOPLE WITH LIMITED MOBILITY. PUBLIC VEHICULAR ACCESS BEYOND THIS POINT SHOULD BE RESTRICTED.
- PROVIDE A 1:14 PATH/RAMP WITH BALUSTRADE AS ADDITIONAL UNIVERSAL ACCESS BETWEEN THE MAIN ENTRANCE AND THE WESTERN CORNER.
- WITHIN THE MEMORIAL GARDENS MAIN PATHS SHOULD BE 2.5M WIDE TO FACILITATE STAFF VEHICLES AND TREE MAINTENANCE EQUIPMENT ACCESS THROUGHOUT. SECONDARY PATHS SHOULD BE 1.2M MINIMUM.
- CREATE MEANDERING PATHS LINKING POCKETS OF GARDENS FOR ASH INTERMENTS, IN INFORMAL LANDSCAPE SETTING.
- USE ARTWORK THROUGHOUT.
- PROVIDE VARIETY OF CREMATED PLACEMENTS:
  - NICHE WALLS (SIMILAR TO NEW ONES – TAKING ALL OF THE ASHES) (GOOD)
  - RETAINING WALL – TOP OF WALL POSITIONS (BETTER)
  - AROUND EXISTING AND NEW TREES (INDIVIDUAL AND FAMILY)(BETTER)
  - GARDEN BED EDGES (WITH DEFINED PRIVATE SPACE, AND URN RECEPTACLE BELOW GROUND TO MIMINISE DIGGING REQUIREMENTS AND SAVE TIME)(GOOD, BETTER BEST DEPENDING ON DESIGN)
  - PROVIDE IRRIGATION TO ALL GARDEN BEDS TO ENSURE QUALITY LANDSCAPE.

AREA (2) : ROUNDABOUT (UPDATED 2025)

- CONSERVE THE GREEN CIRCULAR SHAPE AS AN IMPORTANT PART OF THE ORIGINAL LAYOUT.
- PROVIDE 2 ROWS OF PARKING REINFORCED GRASS (GRASS PAVE OR OTHERWISE APPROVED) TOGETHER WITH WHEEL STOPS.
- RETAIN ALL EXISTING TREES. REPLACE THEM WHEN NEEDED.
- DEVELOP MEMORIAL GARDENS WHERE SHOWN.

AREA (3) : (UPDATED 2025)

- EXTEND LAWN GRAVES.
- ENSURE SUITABLE SPACE IS LEFT TO ALLOW FOR TREE PLANTING TO COMPLETE ENTRANCE AVENUE PLANTING.

AREA (4) : GRAVE INFILL (UPDATED 2025)

- A: INFILL OLD GRASSED ROAD WITH MONUMENTAL GRAVES. EXISTING CONCRETE ROADS PROVIDE SUFFICIENT ACCESS TO MONUMENTAL SECTION
- B: EXTEND LAWN GRAVES
- C: MONUMENTAL GRAVES – LAID OUT DOUBLE SIDED FOR SPACE EFFICIENCIES.
- D: RETAIN A 1.2M WIDE PATH IN THE ALIGNMENT OF THE OLD ROAD, WITH A COMBINATION OF LAWN GRAVES, ASH PLACEMENTS AND MONUMENTAL GRAVES WITH CONSIDERATION FOR MAINTENANCE ACCESS.

THESE AREAS WILL BE THE LAST TO BE DEVELOPED WHEN THE CEMETERY HAS RAN OUT OF GRAVES. ACCESS ROADS ARE THEN EXPECTED TO BE LIFTED AND TURNED INTO BURIAL AREAS. NEW GRAVES SHOULD BE IN KEEPING WITH EXISTING STOCK (E.G. MONUMENTAL IN EXISTING MONUMENTAL SECTION, LAWN GRAVES IN OR CLOSE TO EXISTING LAWN SECTION) TO RETAIN THE CHARACTER OF THE AREA.

AREA (5A) : CHILDREN SECTION (UPDATED 2025)

- CHILDREN GRAVES (16 NO.)
- PROVIDE PATH MEANDERING THROUGH EXISTING CASUARINAS, WITH RESPITE AREAS AND SCULPTURE ONTO WHICH MESSAGES CAN BE DRAWN (CHALKS) AND PAPER MESSAGES CAN BE ATTACHED TO TREES. PROVIDE IMAGINATIVE AND INFORMAL PLAY ELEMENTS FOR CHILDREN ENTERTAINMENT TO ENABLE PARENTS TO TEND TO THEIR CHILD'S GRAVE AND GRIEVE.
- CARRY OUT GEOTECHNICAL REVIEW TO AREAS TO MAP OUT CONSTRAINTS.

AREA (5B) : SHELTER (UPDATED 2025)

ALTHOUGH THE SHELTER IS TO BE USED BY ALL ATTENDEES AND VISITORS, THE MAJORITY OF VISITORS USING IT ARE OF MACEDONIAN DESCENT, INVOLVING FEASTING AND SOCIAL GATHERINGS. IT IS THEREFORE IMPORTANT TO CONSIDER ITS ACCESSIBILITY AND DISTANCE TO CAR PARKING AND TOILETS. A CENTRAL LOCATION IS PREFERRED AND DDA COMPLIANT ACCESS IS ESSENTIAL. IT IS PROPOSED TO RELOCATE NEXT TO AREA 5A. IT SHOULD BE NOTED THAT WHEN THE CEMETERY HAS REACHED CAPACITY, IT CAN BE REMOVED AND THE AREA DEVELOPED AS LAWN GRAVE.

AREA (6) : ENTRY DRIVEWAY (UPDATED 2025)

- PROVIDE PARALLEL PARKING ALONG ENTRANCE ROAD (ON ONE SIDE ONLY). FILL AREA AND CONSTRUCT RETAINING WALL TO DEAL WITH LEVEL CHANGES.
- OFFER NEW PRODUCT IN WALL (HEADSTONE IN WALL WITH LAWN GRAVES IN FRONT) (BEST)
- INTERRUPT PARKING BAYS TO ALLOW FOR TREE PLANTING TO FOLLOW ROAD ALIGNMENT TO PROVIDE BETTER ENTRY PRESENTATION AND SHADE TO CARS.

AREA (7) : TOILETS

- NEW TOILET
- PROVIDE LARGE CONCRETE APRON ALL AROUND.

AREA (8) : MEMORIAL

- LARGE FLAT/SAWN SEATING STONES LAID FLAT AND RANDOMLY FOR RESPITE AMONGST THE TREES AND WAITING SPACE FOR TOILET.
- POSSIBLE LOCATION FOR RSL COMMEMORATIVE ROCK.

AREA (9) : STORAGE BAYS

UPGRADE STORAGE BAYS WITH SCREENING AND GATED ACCESS.

AREA (10) : STAFF AMENITIES (UPDATED 2025)

- PROVIDE SMALL LUNCH/WAITING ROOM FOR STAFF, CLOSE TO TOILETS AND STORAGE BAYS.

AREA (11) : FENCING

- ESTABLISH SCREEN PLANTING. HEIGHT TO BE ESTABLISHED THROUGH CONSULTATION WITH ADJACENT PROPERTY OWNERS.

AREA (12) : CRYPTS

- POTENTIAL ABOVE-GROUND BURIALS UNITS, MAXIMUM 2 LEVELS HIGH, LINKED BY LOW ONE-SIDED NICHE WALLS/RAISED PLANTERS, BOTH ACTING AS RETAINING WALLS. TO BE IMPLEMENTED PROGRESSIVELY AND BASED ON DEMAND. TREES SHOULD BE RETAINED UNTIL THEY BECOME SENESCENT, AFTER WHICH TIME CONSTRUCTION OF NICHE WALLS MAY OCCUR PROGRESSIVELY.
- UPGRADE FENCING TO BUS DEPOT, TO MATCH FRONT METAL PICKET FENCING.

AREA (13) : FRONTAGE

- INFILL GARDEN BED WITH LOW SCREEN PLANTING TO SOFTEN VISUAL IMPACT OF CEMETERY & IMPROVE STREET PRESENTATION.

NOTE:

- PROPOSED WORKS ARE SUBJECT TO FURTHER HERITAGE STUDIES AND OTHER PLANNING DETAILED REVIEWS.
- CONSIDER COLLECTING WATER OFF STRUCTURES FOR STORAGE AND USE ON SITE FOR LANDSCAPING.

DRAWN BY: TV
SHEET NO: 01/07

SCALE: 1:500@A1

ISSUE	DESCRIPTION	DATE	REVISION
APPR.	CLIENT	04/02/20	
C. CONS	CLIENT	21/02/20	A
APPR.	COUNCIL	13/08/20	B
FINAL	COUNCIL	22/02/21	C
FINAL	COUNCIL	03/04/2025	D
FINAL	COUNCIL	07/05/2025	E

CLIENT:
SHELLHARBOUR CEMETERY

TITLE: MASTERPLAN
DRAWING NO: SK01C

DATE: 07.05.2025
PROJECT NO:1904

PROJECT NAME:
SHELLHARBOUR CEMETERY, NSW

A: 1/17 Rex Avenue, Alphington VIC 3078
E: flo@fjla.com.au
M: 0419 983 641

Florence Jaquet
Landscape Architect
Cemetery Specialist